

Evaluation of Determination, Enforcement, Regulation and Monitoring of Entitlement in Pilot Projects for the Rabi & Hot Weather Seasons 2010-11

- 1.0 In the year 2006-07, the concept of Entitlement was initiated with 5 pilot projects from the Krishna basin as per the provision in Section 11(a) of MWRRA Act, 2005. The Entitlement Programme extended over the years. The number of projects covered under the Programme is:-

	Addition during the year					No. of projects
Year	2006-07	2007-08	2008-09	2009-10	2010-11	Total
2006-07	5					5
2007-08		15				20
2008-09			57			77
2009-10				52		129
2010-11					100	229

During the year 2010-11 the number of Water User Associations (WUAs) covered under the Programme is 527.

- 1.1 Category-wise and river basin-wise abstract of the 229 pilot projects considered under the Entitlement Programme for 2010-11:

Sr. No.	Category of Project	River Basin					WUAs under Entitlement
		Godavari	Krishna	Tapi	Konkan	Total	
1	Major	8	2	1	1	12	203
2	Medium	9	2	2	0	13	71
3	Minor	97	50	32	26	204	253
	Total	114	54	35	27	229	527

- 1.2 Of the 229 pilot projects considered under the Entitlement Programme 24 projects are not included in the Maharashtra Water Sector Improvement Project (MWSIP). The other 205 projects are from the MWSIP. The year

wise break-up of pilot projects under MWSIP considered under the monitoring and implementation of Entitlement Programme is-

Sr. No.	Irrigation Year	Project Category							
		Major		Medium		Minor		Total	
		Projects	WUAs	Projects	WUAs	Projects	WUAs	Projects	WUAs
1	2006-07	2	20	1	8	2	2	5	30
2	2007-08	4	25	4	41	11	14	19	80
3	2008-09	5	28	8	49	40	50	53	127
4	2009-10	5	28	10	53	90	105	105	186
5	2010-11	9	200	11	68	185	233	205	501

1.3 Year wise break-up of pilot projects outside MWSIP is -

Sr. No.	Irrigation Year	Project Category							
		Major		Medium		Minor		Total	
		Projects	WUAs	Projects	WUAs	Projects	WUAs	Projects	WUAs
1	2006-07	0	0	0	0	0	0	0	0
2	2007-08	1	1	0	0	0	0	1	1
3	2008-09	3	3	2	3	19	20	24	26
4	2009-10	3	3	2	3	19	20	24	26
5	2010-11	3	3	2	3	19	20	24	26

2.1 Annexure I gives list of all the 229 pilot projects giving break-up of total number of WUAs of the projects vis-a-vis number of WUAs included in the Entitlement Programme, corresponding WUAs area under Entitlement, total number of beneficiaries covered under the Entitlement Programme.

2.2 As per provisions in MWRRA Act, 2005 (Maharashtra Act No. XVIII of 2005), clause 11(g),function of MWWRA is to lay down the criteria and monitor the issuance of Entitlement and as per provisions in clause

11(g)(iii), Bulk Water Entitlements for irrigation shall be issued by River Basin Agency to the Water Users Associations. Applicable Unit Water Use Entitlements on the basis of storage as on 15/10 were checked and communicated to field officers for all 229 projects under consideration, because the Entitlement programme is being implemented on pilot basis. However, in future Entitlement Criteria will be evolved by MWRRA and entitlements for irrigation will be issued by RBAs.

2.3 Annexure II (A) gives details of all the 229 projects where Entitlement Programme is implemented in Rabi season of the year 2010-11. The details such as number of WUAs actually covered under the Entitlement Programme, their corresponding area, corresponding applicable Entitlement in Thousand Cubic Metres (TCM) vis-a-vis actual quantity delivered in the Rabi season and corresponding area irrigated in Rabi & number of beneficiaries are tabulated in this Annexure.

3.0 Performance Evaluation of Pilot Projects (2010-11)

3.1 Entitlement Programme for Rabi

3.1.1 Percentage of Entitlement Delivered:

Applicable entitlement for all 229 pilot projects is checked and communicated. The basis is the live storage as on 15 October 2010. The percentage of Entitlement delivered in Rabi (Tcum) with respect to the Applicable entitlement (Tcum), in various ranges during the Rabi season is given below.

% of Entitlement delivered in Rabi season

Serial Number	Range of % of Entitlement delivered in Rabi season w.r.t. the Applicable Entitlement	Number of projects	Cumulative number of projects
1	2	3	4
1	Above 125	12	12
2	100 to < 125	17	29
3	90 to < 100	11	40
4	80 to < 90	18	58
5	70 to < 80	16	74

Serial Number	Range of % of Entitlement delivered in Rabi season w.r.t. the Applicable Entitlement	Number of projects	Cumulative number of projects
6	60 to < 70	20	94
7	50 to < 60	23	117
8	40 to < 50	19	136
9	30 to < 40	16	152
10	20 to < 30	15	167
11	10 to < 20	14	181
12	> 0 to < 10	8	189
13	0	39	228
14	Project deleted	1	229

One pilot i.e. Navegaon Bandha is deleted.

The '0' deliverance of entitlement at 39 projects is attributed to the reasons indicated in the following table -

Reasons for not availing Entitlement

Reasons for not availing Entitlement	Number of Projects	Names of projects	reference serial number
A)No demand either in Rabi or in HW	Sixteen projects		
		1) Anjani	15
		2)Dhakani	32
		3)Sidhanath	36
		4)Dudhebhavi	37
		5)Belgaon	61
		6)Rengepar	78
		7)Satewadi	81
		8)Dighanchi	83
		9)Akharga	93
		10)Gothala	109
		11)Neoli	110
		12)Hingangaon	141
		13)Shegaon	144
		14)Dharur	189
		15)Tintraj	212
		16)Ankhoda	226

B)Saved for HW	Seven projects		
		1)Mangi	3
		2)Yamai	66
		3)Hanjagi	86
		4)Shirvalwadi	87
		5)Rampur	148
		6)Ghoddhari	182
		7) Lagam	228
C)Water saved for HW , but HW irrigation also not exercised	one project		
		1)Badrakha	69
D)Less delta available (due to less storage)	one project		
		1)Paratwadi	209
E)Canal system not functioning/ canal rehabilitation work in progress / incomplete rehabilitation works	Fourteen projects		
		1)Shewaga	68
		2)Wafgaon	136
		3)Alegaon Paga	137
		4)Pimpoli	138
		5)Walen	139
		6)Mahur	140
		7)Shirwali	162
		8)Kalwande	163
		9)Vhel	164
		10)Harkul	169
		11)Shirwal	170
		12)Madkhol	171
		13)Pimprala	175
		14)Velhale	215
Total number of projects not availing Rabi irrigation	Thirty nine		

3.1.2 Percentage of area irrigated

Annexure II (A) gives the delineated area of WUAs under the entitlement, vis-a-vis actual area irrigated and percentage of area irrigated to the

delineated area. An abstract of % of area irrigated during Rabi of 2010-11 is given below.

Sr. No.	Range of % of actual irrigated area to the delineated area	Number of projects	Cumulative number of projects
1	2	3	4
1	80 to 100	4	4
2	60 to < 80	7	11
3	50 to < 60	9	20
4	30 to < 50	40	60
5	10 to < 30	93	153
6	> 0 to < 10	36	189
7	0	39	228
8	Project deleted	1	229

3.1.3 Evaluation of performance is made on the basis of % entitlement delivered, % of actual area irrigated and % number of beneficiaries covered.

Annexure II (A) presents project wise break up of :

- i) % of Entitlement delivered as against the total applicable entitlement due
- ii) % of actual area irrigated as against the total delineated area of WUAs
- iii) % of beneficiaries (members) received entitlement as against the total number of WUAs.

Performance of 2 projects viz. Dongargaon (Wardha) & Kannamwar gram M.I (Wardha) stands out remarkable as

- i) Actual area irrigated is more than 80 %.
- ii) % entitlement deliver is more than 70 %.
- iii) % of beneficiaries receiving entitlement against total no. of members is greater than 85 %.

3.2 Entitlement Programme for Hot Weather

3.2.1 After completion of irrigation in the Rabi season during the year 2010-11 on these 189 pilot projects, Hot Weather irrigation is exercised on 54 pilot projects as water was available and also there was demand from WUAs for Hot Weather irrigation. In the Annexure II(B) entitlement scenario of such projects is presented. In addition to these projects, hot weather rotations as a part of continuous Kokan-Hangam (i.e. Rabi plus hot weather starting from December & lasting till April) for paddy irrigation are given in projects from Konkan region & also few projects from Vidarbha region, for which season starts from January & lasts till May These projects are already included in Rabi Entitlement Programme.

3.2.2 Performance Evaluation of Entitlement Programme on Pilot Projects in Hot Weather

Hot Weather Entitlement Programme was implemented on 54 pilot projects. Out of 39 projects where 0% entitlement is availed in Rabi, 7 projects are such that WUAs have deferred the Rabi Entitlement so as to avail the Entitlement in Hot Weather season. These projects are Mangi, Yamai, Hanjagi, Shirvalwadi, Rampur, Ghoddhari & Lagam.

3.2.3 On the basis of storages as on 28.02.2011, field officers computed the Applicable Entitlement for Hot Weather. An abstract of entitlement delivered in various ranges is given below.

% of Entitlement delivered

Sr. No	Range of % of Entitlement delivered in Hot Weather	Number of projects	Cumulative number of projects
1	2	3	4
1	above 125	5	5
2	100 to < 125	3	8
3	90 to < 100	6	14
4	80 to < 90	4	18
5	70 to < 80	5	23
6	60 to < 70	3	26
7	50 to < 60	2	28
8	40 to < 50	5	33

Sr. No	Range of % of Entitlement delivered in Hot Weather	Number of projects	Cumulative number of projects
9	30 to < 40	2	35
10	20 to < 30	5	40
11	10 to < 20	6	46
12	> 0 to < 10	8	54

3.2.4 An abstract of percentage area irrigated during hot weather is given below:

Percentage area irrigated during hot weather

Sr. No	Range of % of actual area irrigated in HW to the delineated area	Number of pilot projects	cumulative number of projects
1	2	3	4
1	50 to < 60	1	1
2	40 to < 50	0	1
3	30 to < 40	3	4
4	20 to < 30	9	13
5	10 to < 20	13	26
6	> 0 to < 10	28	54

4.0 Inspection by Regulators

Annexure II (A) & II (B) give project wise number of visits during the rotations by the appointed regulators. As per the Technical Manual brought out by the Authority in 2007, a regulator has to make at least 3 random checks in a rotation period of 15 days or so. It is seen that on most of the projects, regulators could pay only 1 visit per rotation.

Impact of Regulators:

Enforcement of entitlements is one of the functions of MWRRA devolved by the Act. In order to monitor the enforcement of entitlements, MWRRA appoints regulators on the recommendation of the Water Resources Department. They are specially trained for the task they are intended to perform.

The Entitlement Programme implemented on pilot irrigation projects in the State during the period 2007-08 to 2010-11 has positively testified the performance of regulators which is clear from the following :-

- (i) There is a provision in the powers & responsibilities of Regulators to issue Pink slips, so that deficiency in operations could be rectified. Pink slip is issued by the Regulator to the Department's staff when the quantum supplied in any rotation is short by 15-20% of the agreed quantum. It is required to make good the shortfall in subsequent rotation.

Critical remarks in respect of deficient installation of measuring devices, improper field condition of canal system have been reported by regulators. This helped speed up undertaking corrective / remedial measures.

- (ii) Regulators have cross checked the quantities supplied by the field officers and have reported the same.
- (iii) Regulators have reported the requirements and requests of the WUAs to field officers and accordingly the action is taken by the field officers to set the matters right.
- (iv) Since the regulators are appointed by MWRRA and are to report directly to it, they have worked as representatives of MWRRA.
- (v) Regulators have visited at least once during every rotation and acted as an inter face between the WUAs and the Department's officials (RBAs).

5.0 Workshop on Operationalising Water Entitlement

The objective of organizing workshop on Operationalising Water Entitlement is to have an interaction among service provider, managerial staff of WUAs and regulators (functioning on behalf of Authority). Such workshops provide an opportunity to present success stories of WUAs which have benefitted by way of implementation of Entitlement Programme. Other WUAs get inspiration through this for performance enhancement so that overall water use efficiency is further increased.

Regional Workshops at Nagpur & Aurangabad were organized, on 17/09/2010, & 04/10/2010, respectively. Workshops scheduled to be organized at Amaravati & Ratnagiri were cancelled due to some unavoidable reason, then combined workshop was organized at Pune on 15/10/2010, and concerned regulators, field officers, representatives of WUAs attended the workshop at Pune.

Regulators were introduced to their functions and duties as far as delivering entitlements was concerned. They are trained through such workshops as to the modus operandi of enforcement of entitlements.

7.0 **Evaluation of Entitlement Programme (2010-11) in Nutshell**

The total number of projects included in Entitlement programme is 229. Out of these 229 projects 205 projects are MWSIP projects & out of 1332 WUAs under these 205 projects 501 WUAs are included in Entitlement programme. MWRRA has planned to focus only on MWSIP projects for inclusion in Entitlement programme, as such Non-MWSIP projects are restricted to 24 projects. Out of 220 WUAs under these Non-MWSIP projects 26 WUAs are included in Entitlement programme. From irrigation year 2010-11, no new Non-MWSIP project will be included. Thus for total number of 1358 WUAs under these 229 pilot projects, 527 WUAs have been included under Entitlement programme 2010-11.

Total delineated area of 527 WUAs included in Entitlement programme so far is 220125 ha. Actual area which received entitlement in Rabi 2010-11 is 40068 Ha. & actual area irrigated in HW 2011 is 17470 Ha.

As per provisions in MWRRA Act, 2005, the Entitlement programme is introduced & Determination, Enforcement, Regulation of Entitlement is being implemented from irrigation year 2006-07. At this stage, the works of rehabilitation of distribution system and also the works of dam/dam components as proposed by DSRP are under progress and the concept of issuance & enforcement on volumetric basis, with legal backing is newly introduced. It will take some time to get momentum for this concept of reforms.

ANNEXURE – I**Pilot Projects for Entitlement for the Year for 2010-11**

Sr.No.	Name of Project	Whether included in MWSIP	Basin	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.
	2006-07						
	Major						
1	Kukadi	Yes	Krishna	117	10	6080	8029
2	Ghod	Yes	Krishna	55	10	5002	6042
	Medium						
3	Mangi	Yes	Krishna	8	8	3495	3628
	Minor						
4	Diwale	Yes	Krishna	1	1	1145	323
5	Benikre	Yes	Krishna	1	1	311	358
	2007-08						
	Major						
6	Lower Manar	Yes	Godavari	39	3	1132	1929
7	Hatnur	Yes	Tapi	56	2	759	802
8	Lower Wunna	NO	Godavari	12	1	186	623
	Medium						
9	Katepurna	Yes	Tapi	32	7	1308	2146
10	Waghad	Yes	Godavari	24	24	15916	9642
11	Panzara	Yes	Tapi	19	2	569	573
	Minor						
12	Hiware	Yes	Krishna	1	1	833	517
13	Nandwal	Yes	Krishna	1	1	964	342
14	Banganga	Yes	Krishna	3	3	1936	1630
15	Anjani	Yes	Krishna	1	1	704	499
16	Chincholi	Yes	Krishna	2	2	679	926
17	Ambegaon	Yes	Godavari	1	1	325	649
18	Bhutekarwadi	Yes	Godavari	1	1	922	1067
19	Botezari	Yes	Godavari	1	1	337	611
20	Dongargaon (W)	Yes	Godavari	1	1	306	609

Sr.No.	Name of Project	Whether included in MWSIP	Basin	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.
	2008-09						
	Major						
21	Mula	Yes	Godavari	303	113	45241	41421
22	Ozarkhed	NO	Godavari	27	1	246	479
23	Palkhed	NO	Godavari	143	1	378	495
	Medium						
24	Koradi	Yes	Godavari	13	1	145	164
25	Sukhana	Yes	Godavari	11	7	2065	1310
26	Gharni	Yes	Godavari	8	2	779	1299
27	Ghatsilpargaon	Yes	Godavari	6	4	2434	1179
28	Chulband	NO	Godavari	2	2	870	1017
29	Kolar	NO	Godavari	16	1	172	172
	Minor						
30	Kankatrewadi	NO	Krishna	1	1	295	190
31	Shiraswadi	NO	Krishna	1	1	457	275
32	Dhakani	NO	Krishna	1	1	443	501
33	Tambave	Yes	Krishna	2	2	2843	1808
34	Manapadale	Yes	Krishna	1	1	1240	436
35	Atpadi	Yes	Krishna	2	2	2334	1170
36	Sidhanath	Yes	Krishna	1	1	662	872
37	Dudhebhavi	NO	Krishna	1	1	672	745
38	Chare	NO	Krishna	1	1	298	368
39	Kalambwadi	NO	Krishna	1	1	328	648
40	Mamdapur	NO	Krishna	1	1	410	360
41	Walwad	NO	Krishna	1	1	190	254
42	Deocope	Yes	WF	1	1	69	105
43	Aundha	NO	Godavari	1	1	327	402
44	Kakaddhaba	NO	Godavari	1	1	447	449
45	Suregaon	NO	Godavari	1	1	544	445
46	Wadad	NO	Godavari	1	1	172	220
47	Mulzara	Yes	Godavari	1	1	587	818
48	Nichpur	Yes	Godavari	1	1	434	525
49	Sugaon	Yes	Godavari	1	1	881	715

Sr.No.	Name of Project	Whether included in MWSIP	Basin	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.
50	Dastapur	Yes	Godavari	1	1	318	405
51	Nanduri	NO	Tapi	1	1	164	313
52	Dhamangaon Deshmukh	NO	Tapi	1	1	206	324
53	Ghoti	Yes	Godavari	1	1	152	493
54	Anji	NO	Godavari	1	1	414	775
55	Kolhi	NO	Tapi	1	1	601	758
56	Pardeshwadi	Yes	Godavari	1	1	372	530
57	Banoti	Yes	Tapi	1	1	605	872
58	Bharaj	Yes	Godavari	1	1	864	668
59	Pimparkheda	Yes	Godavari	1	1	445	582
60	Charthana	NO	Godavari	1	1	123	419
61	Belgaon	Yes	Krishna	1	1	604	355
62	Kambali	Yes	Krishna	1	1	694	640
63	Golangri	Yes	Godavari	1	1	527	437
64	Nagthana	Yes	Godavari	3	1	257	492
65	Harani	Yes	Krishna	12	7	660	1837
66	Yamai	Yes	Krishna	2	2	147	492
67	Mohri	Yes	Godavari	1	1	920	357
68	Shewaga	Yes	Tapi	2	1	168	411
69	Badrakha	Yes	Tapi	1	1	358	335
70	Galan	Yes	Tapi	1	1	320	340
71	Nawegaon Bandh	NO	Godavari	2	2	797	3113
72	Khapri	NO	Godavari	1	1	272	566
73	Ambazari	Yes	Godavari	1	1	316	620
74	Anji Bhorkhed	Yes	Godavari	1	1	284	596
75	Umari	Yes	Godavari	1	1	282	749
76	Ashti	Yes	Godavari	1	1	301	351
77	Kannamwargram	Yes	Godavari	1	1	198	341
	2009-10						
	Medium						
78	Rengepar	Yes	Godavari	4	2	428	449
79	Kanholinala	Yes	Godavari	6	6	1786	3497

Sr.No.	Name of Project	Whether included in MWSIP	Basin	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.
	Minor						
80	Pilanwadi	Yes	Krishna	1	1	514	419
81	Satewadi	Yes	Krishna	1	1	393	162
82	Shendhri	Yes	Krishna	1	1	1461	314
83	Dighanchi	Yes	Krishna	1	1	722	742
84	Kuchi	Yes	Krishna	1	1	650	392
85	Lingnur	Yes	Krishna	1	1	680	308
86	Hanjagi	Yes	Krishna	1	1	234	418
87	Shirvalwadi	Yes	Krishna	2	2	752	655
88	Pathari	Yes	Krishna	2	2	772	1114
89	Padvalkarwadi	Yes	Krishna	2	2	597	475
90	Hotagi	Yes	Krishna	2	2	792	1199
91	Raitale	Yes	WF	1	1	70	67
92	Bothi	Yes	Godavari	1	1	454	660
93	Akharga	Yes	Godavari	1	1	154	378
94	Isapur	Yes	Tapi	1	1	124	243
95	Kanadi	Yes	Tapi	1	1	172	333
96	Mozari	Yes	Tapi	1	1	297	583
97	Pimpalgaon Hande	Yes	Tapi	1	1	122	239
98	Khatijapur	Yes	Tapi	2	2	284	519
99	Saraswati	Yes	Godavari	1	1	250	324
100	Zari	Yes	Godavari	1	1	254	293
101	Telhara	Yes	Godavari	1	1	204	308
102	Andera	Yes	Godavari	1	1	207	241
103	Pimpalgaon Nath	Yes	Tapi	1	1	320	405
104	Eklara	Yes	Godavari	1	1	214	372
105	Khadakdoh	Yes	Godavari	1	1	253	661
106	Motsawanga	Yes	Godavari	1	1	509	864
107	Ranjangaon	Yes	Godavari	1	1	297	364
108	Konad	Yes	Godavari	1	1	1212	1346
109	Gotala	Yes	Godavari	1	1	568	937
110	Neoli	Yes	Godavari	1	1	267	399
111	Kasarbalkunda	Yes	Godavari	2	1	562	834

Sr.No.	Name of Project	Whether included in MWSIP	Basin	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.
112	Bagalwadi	Yes	Krishna	1	1	150	441
113	Bhalwani	Yes	Godavari	1	1	932	650
114	Tikhoh	Yes	Godavari	1	1	860	340
115	Ekalhare	Yes	Godavari	1	1	133	351
116	Ramshej	Yes	Godavari	1	1	212	530
117	Chougaon	Yes	Tapi	1	1	790	490
118	Kothare	Yes	Tapi	1	1	784	737
119	Nimgul	Yes	Tapi	1	1	235	400
120	Mitgaon	Yes	Tapi	1	1	88	128
121	Hatgaon	Yes	Tapi	1	1	153	441
122	Kankaraj	Yes	Tapi	1	1	527	438
123	Urkudapar	Yes	Godavari	2	1	285	581
124	Suwardhara	Yes	Godavari	1	1	205	547
125	Zilpa	Yes	Godavari	1	1	157	352
126	Satighat	Yes	Godavari	1	1	257	485
127	Ukarvahi	Yes	Godavari	1	1	247	635
128	Kawadi	Yes	Godavari	1	1	125	226
129	Savangi	Yes	Godavari	1	1	141	226
	2010-11						
	Major						
130	Kal-Amba	Yes	WF	24	3	18041	765
131	Upper Pus	Yes	Godavari	30	30	6605	11814
132	Pench	Yes	Godavari	254	21	4265	7201
133	Itiadhoh	Yes	Godavari	55	8	2212	2751
	Medium						
134	Krishna Canal	Yes	Krishna	25	5	3502	1039
	Minor						
135	Shirsuphal	Yes	Krishna	1	1	1155	661
136	Wafgaon	Yes	Krishna	1	1	595	327
137	Alegaon Paga	Yes	Krishna	1	1	871	341
138	Pimpoli	Yes	Krishna	1	1	970	588
139	Walén	Yes	Krishna	1	1	377	941
140	Mahur	Yes	Krishna	1	1	794	432

Sr.No.	Name of Project	Whether included in MWSIP	Basin	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.
141	Hingangaon	Yes	Krishna	1	1	355	312
142	Mayani	Yes	Krishna	1	1	2278	486
143	Pingali	Yes	Krishna	3	3	2724	1538
144	Shegaon	Yes	Krishna	1	1	2013	843
145	Kadegaon	Yes	Krishna	1	1	637	321
146	Kandalgaon	Yes	Krishna	1	1	1131	448
147	Karanjivane	Yes	Krishna	1	1	314	269
148	Rampur	Yes	Krishna	1	1	365	486
149	Awasare	Yes	WF	1	1	483	146
150	Bhilawale	Yes	WF	1	1	82	100
151	Dongaste	Yes	WF	1	1	189	260
152	Jamburde	Yes	WF	1	1	485	194
153	Kharade	Yes	WF	1	1	290	176
154	Kondgaon	Yes	WF	1	1	251	212
155	Shrigaon	Yes	WF	1	1	169	227
156	Thakurwadi	Yes	WF	1	1	167	119
157	Unhere	Yes	WF	1	1	153	170
158	Usgaon	Yes	WF	1	1	108	113
159	Usran	Yes	WF	1	1	263	182
160	Velholi	Yes	WF	1	1	262	182
161	Varandha	Yes	WF	1	1	274	79
162	Shirwali	Yes	WF	1	1	307	105
163	Kalwande	Yes	WF	1	1	365	112
164	Vhel	Yes	WF	1	1	140	78
165	Tithwali	Yes	WF	1	1	251	133
166	Shirgaon	Yes	WF	1	1	256	63
167	Nileli	Yes	WF	1	1	121	76
168	Oras	Yes	WF	1	1	267	180
169	Harkul	Yes	WF	1	1	287	106
170	Shirwal	Yes	WF	1	1	310	206
171	Madkhol	Yes	WF	1	1	349	98
172	Amboli	Yes	WF	1	1	154	91
173	Karala	Yes	Godavari	1	1	221	510

Sr.No.	Name of Project	Whether included in MWSIP	Basin	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.
174	Kedarnath	Yes	Godavari	1	1	1558	2109
175	Pimprala	Yes	Godavari	1	1	340	897
176	Parola	Yes	Godavari	1	1	510	571
177	Kalamnuri	Yes	Godavari	1	1	699	968
178	Walki	Yes	Godavari	1	1	211	579
179	Marsul	Yes	Godavari	1	1	234	345
180	Purjal	Yes	Godavari	1	1	599	631
181	Keli	Yes	Godavari	1	1	395	504
182	Ghoddhari	Yes	Godavari	1	1	405	498
183	Sawana	Yes	Godavari	1	1	356	410
184	Karanji	Yes	Godavari	1	1	201	488
185	Dudhana	Yes	Godavari	1	1	89	241
186	Nignoor	Yes	Godavari	1	1	407	738
187	Pimpalshenda	Yes	Tapi	1	1	226	353
188	Tuljapur	Yes	Tapi	1	1	90	150
189	Dharur	Yes	Tapi	1	1	160	213
190	Vyaghra	Yes	Tapi	8	8	2258	1970
191	Sirputi	Yes	Godavari	1	1	339	595
192	Koyali	Yes	Godavari	1	1	131	145
193	Sonkhas	Yes	Godavari	1	1	255	405
194	Hiwara (lahe)	Yes	Godavari	1	1	156	301
195	Singdoh	Yes	Godavari	1	1	92	246
196	Asola-Ingole	Yes	Godavari	1	1	344	580
197	Shekdari	Yes	Godavari	9	9	1541	1775
198	Malkhed	Yes	Godavari	6	6	844	1822
199	Satnoor	Yes	Godavari	2	2	292	299
200	Salai	Yes	Tapi	1	1	274	347
201	Manjara	Yes	Godavari	3	3	525	1266
202	Wai	Yes	Godavari	3	3	565	1653
203	Adol	Yes	Godavari	2	2	1052	1061
204	Vidrupa	Yes	Godavari	3	3	1319	1020
205	Devgaon	Yes	Godavari	1	1	264	666
206	Kelgaon	Yes	Godavari	1	1	478	638
207	Mandvi	Yes	Godavari	1	1	224	411

Sr.No.	Name of Project	Whether included in MWSIP	Basin	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.
208	Nakhatwadi	Yes	Godavari	1	1	328	279
209	Paratwadi	Yes	Godavari	1	1	118	170
210	Tandulwadi	Yes	Godavari	1	1	613	566
211	Wadali	Yes	Godavari	1	1	379	622
212	Tintaraj	Yes	Krishna	1	1	255	367
213	Amboli	Yes	Godavari	1	1	2129	607
214	KhadakOzar	Yes	Godavari	2	2	1763	1962
215	Velhale	Yes	Tapi	1	1	831	455
216	Khaparkheda	Yes	Tapi	1	1	185	972
217	Kondawal	Yes	Tapi	1	1	136	279
218	Budaki	Yes	Tapi	1	1	164	395
219	Ambebara	Yes	Tapi	1	1	369	998
220	Dudhakheda	Yes	Tapi	1	1	327	378
221	Khadkuna	Yes	Tapi	1	1	436	1045
222	Khekada	Yes	Tapi	1	1	255	484
223	Aktitola	Yes	Godavari	1	1	214	611
224	Khumari	Yes	Godavari	1	1	303	657
225	Pipariya	Yes	Godavari	1	1	370	460
226	Ankhoda	Yes	Godavari	1	1	449	201
227	Dongargaon (C)	Yes	Godavari	1	1	598	677
228	Legam	Yes	Godavari	1	1	672	384
229	Sondo	Yes	Godavari	1	1	255	713
	Total			1552	527	227087	220124

ANNEXURE-II A
Pilot Projects for Entitlement - Rabi Irrigation for the year 2010-11

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
	2006-07														
	Major														
1	Kukadi	117	10	6080	8029	6872.82	2811	40.90	1	Nil	2689	33.49	5501	90	
2	Ghod	55	10	5002	6042	5963.55	5709.60	95.74	2	2	1407.50	23.29	2065	41	Yes
	Medium														
3	Mangi	8	8	3495	3628	13155	0.00	0.00	0	0	0.00	0.00	0	0	Yes
	Minor														
4	Diwale	1	1	1145	323	1341.42	268.70	20.03	6	6	235.00	72.76	180	16	Yes
5	Benikre	1	1	311	358	777.22	356.73	45.90	2	6	126.00	35.20	245	79	Yes
	2007-08														
	Major														
6	Lower Manar	39	3	1132	1929	8133.00	6880.00	84.59	3	2	742.00	38.47	857	76	
7	Hatnur	56	2	759	802	1966.60	170.30	8.66	4	4	25.00	3.12	43	6	No
8	Lower Wunna	12	1	186	623	2026.28	1312.77	64.79	3	3	155.00	24.89	152	82	No

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
	Medium														
9	Katepurna	32	7	1308	2146	3864.95	1239.48	32.07	6	2	186.37	8.68	175	13	
10	Waghad	24	24	15916	9642	8053.50	4927.82	61.19	3	2	879.01	9.12	1144	7	Yes
11	Panzara	19	2	569	573	545.29	477.98	87.66	3	3	71.55	12.48	113	20	Yes
	Minor														
12	Hiware	1	1	833	517	1069.80	126.00	11.78	2	2	17.40	3.37	31	4	Yes
13	Nandwal	1	1	964	342	836.09	352.40	42.15	2	2	51.30	15.00	152	16	Yes
14	Banganga	3	3	1936	1630	4162.61	1309.00	31.45	3	2	195.00	11.96	357	18	Yes
15	Anjani	1	1	704	499	626.74	0.00	0.00	0	0	0.00	0.00	0	0	
16	Chincholi	2	2	679	926	1090.37	445.00	40.81	2	0	180.00	19.43	182	27	Yes
17	Ambegaon	1	1	325	649	1243.70	401.15	32.25	5	5	21.00	3.24	12	4	Yes
18	Bhutekarwadi	1	1	922	1067	1593.90	225.64	14.16	1	1	85.00	7.97	110	12	Yes
19	Botezari	1	1	337	611	1418.00	1788.46	126.13	5	5	259.20	42.42	238	71	No
20	Dongargaon (W)	1	1	306	609	2864.80	2016.00	70.37	5	5	494.50	81.23	285	93	Yes
	2008-09														
	Major														
21	Mula	303	113	45241	41421	90008.00	15173.00	16.86	2	2	6358.30	15.35	5963	13	Yes
22	Ozarkhed	27	1	246	479	217.95	220.83	101.32	1	1	100.00	20.88	140	57	Yes

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
23	Palkhed	143	1	378	495	259.61	45.67	17.59	1	1	20.00	4.04	43	11	Yes
	Medium														
24	Koradi	13	1	145	164	314.06	273.87	87.20	5	5	112.00	68.29	15	10	No
25	Sukhana	11	7	2065	1310	2121.00	1461.90	68.93	3	3	431.00	32.90	569	28	No
26	Gharni	8	2	779	1299	2316.00	154.80	6.68	2	1	56.00	4.31	40	5	Yes
27	Ghatsilpargaon	6	4	2434	1179	2365.00	958.00	40.51	2	2	208.00	17.64	545	22	Yes
28	Chulband	2	2	870	1017	7026.30	7100.00	101.05	10	0	506.78	49.85	525	60	No
29	Kolar	16	1	172	172	356.56	163.24	45.78	5	5	45.00	26.14	52	30	No
	Minor														
30	Kankatrewadi	1	1	295	190	467.21	174.80	37.41	2	3	32.40	17.05	73	25	No
31	Shiraswadi	1	1	457	275	675.40	189.50	28.06	2	3	28.60	10.40	64	14	No
32	Dhakani	1	1	443	501	1278.55	0.00	0.00	0	0	0	0.00	0	0	Yes
33	Tambave	2	2	2843	1808	5259.06	904.00	17.19	3	2	140.00	7.74	326	11	Yes
34	Manapadale	1	1	1240	436	678.85	108.93	16.05	6	6	15.00	3.44	82	7	Yes
35	Atpadi	2	2	2334	1170	3325.14	1406.00	42.28	1	1	300.00	25.64	282	12	
36	Sidhanath	1	1	662	872	1789.34	0.00	0.00	0	0	0.00	0.00	0	0	
37	Dudhebhavi	1	1	672	745	804.60	0.00	0.00	0	0	0.00	0.00	0	0	
38	Chare	1	1	298	368	730.48	440.26	60.27	2	2	70.10	19.05	87	29	

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
39	Kalambwadi	1	1	328	648	1248.70	267.00	21.38	2	2	85.00	13.12	45	14	
40	Mamdapur	1	1	410	360	787.68	355.28	45.10	2	2	87.35	24.26	70	17	
41	Walwad	1	1	190	254	414.78	218.42	52.66	2	2	40.00	15.75	40	21	
42	Deocope	1	1	69	105	1993.62	1650.00	82.76	15	4	45.74	43.62	34	49	
43	Aundha	1	1	327	402	861.49	847.04	98.32	4	2	159.00	39.55	100	31	
44	Kakaddhaba	1	1	447	449	1158.42	849.72	73.35	4	2	114.00	25.39	170	38	
45	Suregaon	1	1	544	445	926.05	546.51	59.02	4	2	116.00	26.07	130	24	
46	Wadad	1	1	172	220	556.38	740.00	133.00	3	2	90.00	40.91	69	40	
47	Mulzara	1	1	587	818	1033.13	790.00	76.47	4	2	85.00	10.39	80	14	
48	Nichpur	1	1	434	525	1223.78	870.00	71.09	4	1	95.00	18.10	110	25	
49	Sugaon	1	1	881	715	643.50	706.00	109.71	4	3	67.74	9.47	107	12	
50	Dastapur	1	1	318	405	1320.71	870.00	65.87	5	10	68.00	16.79	77	24	No
51	Nanduri	1	1	164	313	1439.49	570.00	39.60	6	12	102.00	32.59	142	87	No
52	Dhamangaon Deshmukh	1	1	206	324	440.64	523.87	118.89	5	5	80.00	24.69	159	77	No
53	Ghoti	1	1	152	493	1430.19	900.00	62.93	6	6	21.00	4.26	22	14	
54	Anji	1	1	414	775	1880.15	1129.00	60.05	6	6	141.00	18.19	130	31	
55	Kolhi	1	1	601	758	2884.19	2580.00	89.45	6	5	527.00	69.53	293	49	
56	Pardeshwadi	1	1	372	530	1073.10	259.06	24.14	2	2	40.00	7.55	44	12	No

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
57	Banoti	1	1	605	872	1865.50	752.00	40.31	3	2	143.79	16.49	150	25	Yes
58	Bharaj	1	1	864	668	1250.80	810.00	64.76	3	2	173.00	25.90	158	18	No
59	Pimparkheda	1	1	445	582	865.40	560.00	64.71	3	3	85.00	14.60	100	22	No
60	Charthana	1	1	123	419	1168.80	445.70	38.13	3	3	62.00	14.80	67	54	No
61	Belgaon	1	1	604	355	1182.80	0.00	0.00	0	0	0.00	0.00	0	0	No
62	Kambali	1	1	694	640	1304.00	1704.61	130.72	4	4	70.68	11.04	65	9	No
63	Golangri	1	1	527	437	950.80	44.61	4.69	2	2	25.00	5.72	35	7	No
64	Nagthana	3	1	257	492	1132.43	616.00	54.40	1	1	123.00	25.00	87	34	Yes
65	Harani	12	7	660	1837	5665.88	4997.00	88.19	1	1	219.00	11.92	112	17	Yes
66	Yamai	2	2	147	492	938.10	0.00	0.00	0	0	0.00	0.00	0	0	Yes
67	Mohri	1	1	920	357	937.80	147.00	15.67	4	4	13.00	3.64	20	2	Yes
68	Shewaga	2	1	168	411	1232.10	0.00	0.00	0	0	0.00	0.00	0	0	No
69	Badrakha	1	1	358	335	890.40	0.00	0.00	0	0	0.00	0.00	0	0	Yes
70	Galan	1	1	320	340	1134.30	262.33	23.13	2	2	116.00	34.12	91	28	Yes
71	Nawegaon Bandh	2	2	797	3113	DEL									
72	Khapri	1	1	272	566	1172.50	1450.30	123.69	4	4	250.00	44.17	175	64	No
73	Ambazari	1	1	316	620	1347.90	1310.34	97.21	4	4	139.55	22.51	176	56	No
74	Anji Bhorkhed	1	1	284	596	1460.40	770.20	52.74	4	4	159.05	26.70	145	51	Yes

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
75	Umari	1	1	282	749	1343.10	1076.49	80.15	4	4	210.45	28.10	159	56	No
76	Ashti	1	1	301	351	1194.60	525.36	43.98	4	4	66.38	18.90	68	23	No
77	Kannamwargram	1	1	198	341	936.00	997.71	106.59	4	4	299.83	87.97	179	90	No
	2009-10														
	Medium														
78	Rengepar	4	2	428	449	1288.20	0.00	0.00	0	0	0.00	0.00	0	0	No
79	Kanholinala	6	6	1786	3497	9993.20	6365.52	63.70	3	5	1161.00	33.20	762	43	No
	Minor														
80	Pilanwadi	1	1	514	419	721.94	370.30	51.29	3	3	133.50	31.86	206	40	
81	Satewadi	1	1	393	162	401.92	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	No
82	Shendhri	1	1	1461	314	1151.75	246.85	21.43	5	5	61.00	19.43	205	14	
83	Dighanchi	1	1	722	742	1315.57	0.00	0.00	0	0	0.00	0.00	0	0	
84	Kuchi	1	1	650	392	1220.30	909.60	74.54	4	4	100.00	25.51	240	37	
85	Lingnur	1	1	680	308	826.52	317.00	38.35	2	1	105.00	34.14	220	32	
86	Hanjagi	1	1	234	418	708.09	0.00	0.00	0	0	0.00	0.00	0	0	Yes
87	Shirvalwadi	2	2	752	655	1928.98	0.00	0.00	0	0	0.00	0.00	0	0	Yes
88	Pathari	2	2	772	1114	3666.44	902.35	24.61	2	2	220.00	19.74	280	36	Yes

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
89	Padvalkarwadi	2	2	597	475	834.10	882.00	105.74	2	1	155.00	32.63	160	27	Yes
90	Hotagi	2	2	792	1199	1830.87	37.33	2.04	1	1	5.60	0.47	2	0	Yes
91	Raitale	1	1	70	67	879.30	1048.00	119.19	15	4	21.35	32.06	36	51	
92	Bothi	1	1	454	660	1738.44	953.00	54.82	5	2	174.00	26.36	80	18	
93	Akharga	1	1	154	378	938.20	0.00	0.00	0	0	0.00	0.00	0	0	
94	Isapur	1	1	124	243	856.58	717.00	83.71	6	2	115.00	47.33	54	44	
95	Kanadi	1	1	172	333	938.06	975.00	103.94	6	2	165.00	49.55	65	38	
96	Mozari	1	1	297	583	1511.72	872.00	57.68	6	3	153.00	26.24	82	28	
97	Pimpalgaon Hande	1	1	122	239	631.4	546.00	86.47	6	2	109.00	45.56	42	34	
98	Khatijapur	2	2	284	519	767.60	767.80	100.03	6	12	188.00	36.22	129	45	No
99	Saraswati	1	1	250	324	835.60	620.00	74.20	5	10	98.00	30.25	89	36	No
100	Zari	1	1	254	293	868.75	511.10	58.83	5	5	169.00	57.68	153	60	No
101	Telhara	1	1	204	308	1258.18	493.34	39.21	4	4	203.00	65.91	218	107	No
102	Andera	1	1	207	241	706.13	636.47	90.13	4	4	218.00	90.46	241	116	No
103	Pimpalgaon Nath	1	1	320	405	1376.19	340.10	24.71	6	6	68.00	16.79	79	25	No
104	Eklara	1	1	214	372	866.02	694.00	80.14	6	4	68.00	18.28	84	39	
105	Khadakdoh	1	1	253	661	1660.2	1230.00	74.09	5	2	163.00	24.66	155	61	
106	Motsawanga	1	1	509	864	1878.34	1270.00	67.61	6	6	138.00	15.97	151	30	

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
107	Ranjangaon	1	1	297	364	743.60	348.00	46.80	4	3	68.00	18.68	87	29	No
108	Konad	1	1	1212	1346	2296.30	910.00	39.63	3	2	129.00	9.58	304	25	No
109	Gotala	1	1	568	937	1329.90	0.00	0.00	0	0	0.00	0.00	0	0	No
110	Neoli	1	1	267	399	1406.60	0.00	0.00	0	0	0.00	0.00	0	0	No
111	Kasarbalkunda	2	1	562	834	1499.60	12.10	0.81	2	1	6.40	0.77	10	2	Yes
112	Bagalwadi	1	1	150	441	598.90	603.00	100.68	3	3	60.00	13.61	80	53	No
113	Bhalwani	1	1	932	650	765.20	410.00	53.58	4	4	76.00	11.69	116	12	Yes
114	Tikhol	1	1	860	340	773.70	410.00	52.99	4	4	101.00	29.71	100	12	Yes
115	Ekalhare	1	1	133	351	1871.90	311.14	16.62	1	1	129.00	36.75	69	52	Yes
116	Ramshej	1	1	212	530	859.30	798.28	92.90	2	2	320.00	60.38	117	55	No
117	Chougaon	1	1	790	490	2640.70	793.80	30.06	3	1	135.00	27.55	12	2	Yes
118	Kothare	1	1	784	737	638.60	1015.89	159.08	3	1	273.00	37.04	252	32	Yes
119	Nimgul	1	1	235	400	872.90	505.70	57.93	3	1	59.00	14.75	65	28	No
120	Mitgaon	1	1	88	128	598.80	414.00	69.14	3	1	58.00	45.31	51	58	No
121	Hatgaon	1	1	153	441	784.20	33.00	4.21	1	0	20.00	4.54	12	8	No
122	Kankaraj	1	1	527	438	598.80	931.00	155.48	3	3	131.00	29.92	140	27	No
123	Urkudapar	2	1	285	581	1444.00	1703.10	117.94	3	3	301.22	51.85	242	85	No
124	Suwardhara	1	1	205	547	453.10	497.60	109.82	4	4	55.00	10.05	105	51	No

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
125	Zilpa	1	1	157	352	8889.20	876.56	9.86	4	4	115.00	32.66	105	67	No
126	Satighat	1	1	257	485	1129.10	816.48	72.31	4	4	138.64	28.60	180	70	No
127	Ukarvahi	1	1	247	635	1035.30	1414.20	136.60	4	4	240.00	37.80	165	67	No
128	Kawadi	1	1	125	226	591.20	541.00	91.51	4	4	122.35	54.14	97	78	No
129	Savangi	1	1	141	226	1219.60	604.12	49.53	4	4	124.04	54.88	116	82	No
	2010-11														
	Major														
130	Kal-Amba	24	3	18041	765	8605.49	240.00	2.79	1	12	7.29	0.95	15	0	
131	Upper Pus	30	30	6605	11814	24454.98	18079.60	73.93	6	6	1735.18	14.69	1778	27	
132	Pench	254	21	4265	7201	22085.00	4711.64	21.33	3	3	1530.63	21.26	1525	36	No
133	Itiadoh	55	8	2212	2751	16578.00	8813.00	53.16	7	2	760.91	27.66	681	31	No
	Medium														
134	Krishna Canal	25	5	3502	1039	6940	3591.00	51.74	12	4	430.19	41.41	1310	37	
	Minor														
135	Shirsuphal	1	1	1155	661	4252.21	645.00	15.17	3	6	131.35	19.87	300	26	
136	Wafgaon	1	1	595	327	1377.00	0.00	0.00	0	0.00	0.00	0.00	0	0	
137	Alegaon Paga	1	1	871	341	454.76	0.00	0.00	0	0.00	0.00	0.00	0	0	
138	Pimpoli	1	1	970	588	1249.67	0.00	0.00	0	0.00	0.00	0.00	0	0	

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
139	Walen	1	1	377	941	3322.43	0.00	0.00	0	0.00	0.00	0.00	0	0	
140	Mahur	1	1	794	432	1420.85	0.00	0.00	0	0.00	0.00	0.00	0	0	
141	Hingangaon	1	1	355	312	880.00	0.00	0.00	0	0.00	0.00	0.00	0	0	Yes
142	Mayani	1	1	2278	486	934.58	883.00	94.48	2	3	176.00	36.21	287	13	No
143	Pingali	3	3	2724	1538	689.02	385.00	55.88	2	2	30.00	1.95	72	3	No
144	Shegaon	1	1	2013	843	2346.91	0.00	0.00	0	0	0.00	0.00	0	0	
145	Kadegaon	1	1	637	321	936.68	957.00	102.17	2	1	30.00	9.35	70	11	
146	Kandalgaon	1	1	1131	448	1229.31	798.00	64.91	3	7	70.00	15.63	334	30	
147	Karanjivane	1	1	314	269	1001.76	338.59	33.80	3	7	45.00	16.73	165	53	Yes
148	Rampur	1	1	365	486	1433.91	0.00	0.00	0	0	0.00	0.00	0	0	Yes
149	Awasare	1	1	483	146	894.40	570.00	63.73	20	4	31.00	21.23	63	13	
150	Bhilawale	1	1	82	100	1365.80	1271.00	93.06	18	3	70.00	70.00	60	73	
151	Dongaste	1	1	189	260	2423.10	1878.00	77.50	12	4	65.00	25.01	36	19	
152	Jamburde	1	1	485	194	1974.16	850.00	43.06	15	7	59.00	30.41	125	26	
153	Kharade	1	1	290	176	1230.06	1159.00	94.22	15	7	45.25	25.71	55	19	
154	Kondgaon	1	1	251	212	2983.26	2619.00	87.79	1	10	58.60	27.64	114	45	
155	Shrigaon	1	1	169	227	2196.23	1959.00	89.20	1	10	80.00	35.24	140	83	
156	Thakurwadi	1	1	167	119	2257.88	400.02	17.72	15	7	22.60	18.95	35	21	

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
157	Unhere	1	1	153	170	1579.47	425.00	26.91	1	5	9.00	5.29	16	10	
158	Usgaon	1	1	108	113	796.87	555.17	69.67	12	4	28.30	24.97	30	28	
159	Usran	1	1	263	182	1282.92	573.00	44.66	10	5	20.18	11.09	63	24	
160	Velholi	1	1	262	182	2048.1	1489.97	72.75	15	8	39.73	21.83	62	24	
161	Varandha	1	1	274	79	511.37	1227.00	239.95	4	3	62.00	78.48	163	59	
162	Shirwali	1	1	307	105	2056.40	0.00	0.00	0	0	0	0.00	0	0	
163	Kalwande	1	1	365	112	10423.00	0.00	0.00	0	0	0	0.00	0	0	
164	Vhel	1	1	140	78	122.60	0.00	0.00	0	0	0	0.00	0	0	
165	Tithwali	1	1	251	133	1172.00	693.00	59.13	9	7	42.15	31.69	74	29	
166	Shirgaon	1	1	256	63	689.90	343.00	49.72	9	7	9.12	14.48	81	32	
167	Nileli	1	1	121	76	1197.60	319.22	26.65	9	9	30.66	40.49	43	36	
168	Oras	1	1	267	180	1773.80	944.40	53.24	8	8	19.81	11.01	112	42	
169	Harkul	1	1	287	106	1535.90	0.00	0.00	0	0	0.00	0.00	0	0	
170	Shirwal	1	1	310	206	2700.30	0.00	0.00	0	0	0.00	0.00	0	0	
171	Madkhol	1	1	349	98	787.50	0.00	0.00	0	0	0.00	0.00	0	0	
172	Amboli	1	1	154	91	1270.50	1350.90	106.33	6	6	25.40	28.07	92	60	
173	Karala	1	1	221	510	1195.44	670.20	56.06	4	2	184.00	36.08	209	95	
174	Kedarnath	1	1	1558	2109	5445.44	4420.00	81.17	4	2	631.00	29.92	695	45	

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
175	Pimprala	1	1	340	897	2213.80	0.00	0.00	0	0	0.00	0.00	0	0	
176	Parola	1	1	510	571	1116.31	380.00	34.04	4	2	37.40	6.55	55	11	
177	Kalamnuri	1	1	699	968	2338.69	1290.00	55.16	5	2	476.00	49.17	270	39	
178	Walki	1	1	211	579	1417.97	578.00	40.76	4	2	18.00	3.11	30	14	
179	Marsul	1	1	234	345	1857.83	1800.00	96.89	5	2	152.00	44.06	90	38	
180	Purjal	1	1	599	631	1588.86	487.39	30.68	5	2	76.00	12.04	85	14	
181	Keli	1	1	395	504	1245.89	757.00	60.76	3	2	79.00	15.67	68	17	
182	Ghoddhari	1	1	405	498	1535.83	0.00	0.00	0	0	0.00	0.00	0	0	
183	Sawana	1	1	356	410	1264.9	612.00	48.38	4	2	56.02	13.66	69	19	
184	Karanji	1	1	201	488	1963.71	576.10	29.34	6	6	93.00	19.06	78	39	
185	Dudhana	1	1	89	241	612.62	500.00	81.62	6	4	27.00	11.20	24	27	
186	Nignoor	1	1	407	738	1791.13	730.00	40.76	4	4	90.00	12.20	86	21	
187	Pimpalshenda	1	1	226	353	931.20	730.00	78.39	6	2	183.00	51.86	128	57	
188	Tuljapur	1	1	90	150	539.70	458.00	84.86	6	2	74.49	49.66	49	54	
189	Dharur	1	1	160	213	564.24	0.00	0.00	0	0	13.00	6.10	10	6	
190	Vyaghra	8	8	2258	1970	864.83	530.71	61.37	2	2	179.00	9.09	166	7	No
191	Sirputi	1	1	339	595	1193.57	1580.00	132.38	5	5	201.00	33.78	181	53	
192	Koyali	1	1	131	145	570.58	300.00	52.58	5	5	31.00	21.38	66	50	

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
193	Sonkhas	1	1	255	405	840.78	780.00	92.77	6	5	145.00	35.80	59	23	
194	Hiwara (lahe)	1	1	156	301	515.31	380.00	73.74	6	6	45.00	14.95	43	28	
195	Singdoh	1	1	92	246	781.54	420.00	53.74	6	6	55.00	22.36	42	46	
196	Asola-Ingole	1	1	344	580	2146.58	310.00	14.44	6	6	37.00	6.38	27	8	
197	Shekdari	9	9	1541	1775	3124.00	2680.00	85.79	5	10	832.00	46.87	1113	72	No
198	Malkhed	6	6	844	1822	4921.22	1870.00	38.00	5	10	290.00	15.92	265	31	No
199	Satnoor	2	2	292	299	326.25	780.00	239.08	5	10	170.00	56.86	110	38	No
200	Salai	1	1	274	347	901.85	540.00	59.88	6	12	128.00	36.89	117	43	No
201	Manjara	3	3	525	1266	2243.35	1900.00	84.69	6	1	147.00	11.61	94	18	
202	Wai	3	3	565	1653	6187.18	5550.00	89.70	6	1	438.00	26.50	302	53	
203	Adol	2	2	1052	1061	5462.03	1250.00	22.89	6	0	217.00	20.45	295	28	
204	Vidrupa	3	3	1319	1020	1311.72	1780.00	135.70	2	0	354.00	34.71	232	18	
205	Devgaon	1	1	264	666	822.70	432.60	52.58	4	4	100.00	15.02	88	33	No
206	Kelgaon	1	1	478	638	993.20	628.32	63.26	2	2	89.26	13.99	101	21	No
207	Mandvi	1	1	224	411	784.80	272.20	34.68	4	4	65.00	15.82	30	13	No
208	Nakhatwadi	1	1	328	279	888.00	610.00	68.69	3	1	65.00	23.30	80	24	No
209	Paratwadi	1	1	118	170	184.50	0.00	0.00	0	0	0.00	0.00	0	0	No
210	Tandulwadi	1	1	613	566	1159.80	139.35	12.02	2	2	30.00	5.30	36	6	No
211	Wadali	1	1	379	622	1777.20	425.70	23.95	4	4	68.00	10.93	126	33	No

Sr. No.	Name of Project	No of WUAs in the Project	WUAs under Entitle ment.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement 2010-11 (Thousand Cum)	Total Water Delivered in Rabi. (Thousand Cum)	% of water delivered in Rabi to Applicable Entitlement	No of rotations in the Rabi season 2010-11	No of visit by regulator in the Rabi season 2010-11	Actual area irrigated in the Rabi season 2010-11 (ha)	% of Irrigated area to WUA area.	No. of farmers taken up Irrigation in the Rabi season 2010-11	% of farmers taken up Irrigation to total farmers under WUA	Whether HW Proposed
212	Tintaraj	1	1	255	367	586.20	0.00	0.00	0	0	0.00	0.00	0	0	No
213	Amboli	1	1	2129	607	1485.60	270.00	18.17	2	2	45.00	7.41	40	2	Yes
214	KhadakOzar	2	2	1763	1962	1696.60	520.00	30.65	1	2	150.00	7.65	219	12	Yes
215	Velhale	1	1	831	455	1209.00	0.00	0.00	0	0	0.00	0.00	0	0	No
216	Khaparkheda	1	1	185	972	1414.10	1859.50	131.50	4	0	63.00	6.48	84	45	No
217	Kondawal	1	1	136	279	924.80	1043.80	112.87	4	0	81.00	29.03	100	74	No
218	Budaki	1	1	164	395	1013.60	752.00	74.19	3	1	115.00	29.15	89	54	No
219	Ambebara	1	1	369	998	901.90	425.30	47.16	3	0	18.00	1.80	15	4	Yes
220	Dudhakheda	1	1	327	378	2255.60	2820.00	125.02	5	3	305.00	80.69	245	75	No
221	Khadkuna	1	1	436	1045	4376.80	696.00	15.90	4	2	459.00	43.92	125	29	No
222	Khekada	1	1	255	484	787.90	600.00	76.15	4	0	6.00	1.24	14	5	Yes
223	Aktitola	1	1	214	611	580.50	344.50	59.35	10	0	16.86	2.76	10	5	No
224	Khumari	1	1	303	657	412.80	309.44	74.96	2	2	15.00	2.28	25	8	No
225	Pipariya	1	1	370	460	558.10	336.08	60.22	10	0	22.86	4.97	32	9	No
226	Ankhoda	1	1	449	201	298.70	0.00	0.00	0	0	0.00	0.00	0	0	No
227	Dongargaon (C)	1	1	598	677	1642.80	377.94	23.01	2	2	96.00	14.18	156	26	No
228	Legam	1	1	672	384	695.40	0.00	0.00	0	0	0.00	0.00	0	0	Yes
229	Sondo	1	1	255	713	545458	231959	42.53	3	3	119.00	16.69	55	22	No
	Grand Total	1552	527	227087	220125	1090916	463917				40068		45044		

ANNEXURE-II B
Pilot Projects for Entitlement - Hot Weather Irrigation for the year 2010-11

Sr. No.	Name of Project	Whether included in MWSIP	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement for the HW season 2011 (Thousand Cum)	Water Delivered in Hot Weather (Thousand Cum)	% of water delivered in HW to Applicable Entitlement	No of rotations in the HW season 2011	No of visit by regulator in the HW season 2011	Actual area irrigated in the HW season 2011 (ha)	% of Irrigated area to WUA area	No. of farmers taken up Irrigation in the HW season 2011	% of farmers taken up Irrigation to total farmers under WUA
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
	2006-07														
	Major														
1	Kukadi	Yes	117	10	6080	8029	3238	2169.00	66.99	1	0	738.00	9.19	1135	19
2	Ghod	Yes	55	10	5002	6042.10	13919	5124.10	36.81	2	2	1315.20	21.77	1797	36
	Medium														
3	Mangi	Yes	8	8	3495	3627.9	13155	11997.75	91.20	4	4	2114.00	58.27	1626	47
	Minor														
4	Diwale	Yes	1	1	1145	323	857	144.21	16.83	4	4	107.00	33.13	93	8
5	Benikre	Yes	1	1	311	358	421	364.32	86.54	2	4	100.00	27.93	245	79
	2007-08														
	Major														
6	Lower Manar	Yes	39	3	1132	1929	1253	950.00	75.82	5	5	79.00	4.10	207	18
	Medium														
7	Waghad	Yes	24	24	15916	9642	7723	4732.98	61.29	2	2	1088.30	11.29	1380	9

Sr. No	Name of Project	Whether included in MWSIP	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement for the HW season 2011 (Thousand Cum)	Water Delivered in Hot Weather (Thousand Cum)	% of water delivered in HW to Applicable Entitlement	No of rotations in the HW season 2011	No of visit by regulator in the HW season 2011	Actual area irrigated in the HW season 2011 (ha)	% of Irrigated area to WUA area	No. of farmers taken up Irrigation in the HW season 2011	% of farmers taken up Irrigation to total farmers under WUA
	Minor														
8	Banganga	Yes	3	3	1936	1629.84	2283	935.00	40.95	3	1	88.00	5.40	238	12
9	Chincholi	Yes	2	2	679	926.40	608	284.20	46.77	2	1	86.00	9.28	91	13
10	Bhutekarwadi	Yes	1	1	922	1067	670	149.33	22.29	2	1	25.00	2.34	40	4
11	Dongargaon (W)	Yes	1	1	306	608.76	562	568.00	101.07	5	5	27.60	4.53	38	12
	2008-09														
	Major														
12	Mula	Yes	303	113	45241	41421	72801	57858.55	79.47	4	4	8418.50	20.32	2347	5
13	Ozarkhed	NO	27	1	246	479	240	249.37	104.06	1	1	101.00	21.09	140	57
	Medium														
14	Gharni	Yes	8	2	779	1299	1669	63.58	3.81	2	1	25.90	1.99	27	3
15	Ghatsilpargaon	Yes	6	4	2434	1179	539	103.00	19.13	1	1	33.00	2.80	144	6
	Minor														
16	Dhakani	NO	1	1	443	501	1279	150.00	11.73	2	1	17.00	3.39	39	9
17	Tambave	Yes	2	2	2843	1807.86	1625	1150.00	70.77	2	1	117.00	6.47	142	5
18	Manapadale	Yes	1	1	1240	436	456	237.00	51.97	3	3	48.50	11.12	95	8
19	Atpadi	Yes	2	2	2334	1170	1580	252.00	15.95	2	2	18.65	1.59	45	2
20	Dudhebhavi	NO	1	1	672	745	4217	56.62	1.34	1.00	1.00	6.00	0.81	12.00	2

Sr. No	Name of Project	Whether included in MWSIP	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement for the HW season 2011 (Thousand Cum)	Water Delivered in Hot Weather (Thousand Cum)	% of water delivered in HW to Applicable Entitlement	No of rotations in the HW season 2011	No of visit by regulator in the HW season 2011	Actual area irrigated in the HW season 2011 (ha)	% of Irrigated area to WUA area	No. of farmers taken up Irrigation in the HW season 2011	% of farmers taken up Irrigation to total farmers under WUA
21	Banoti	Yes	1	1	605	872	746	317.84	42.63	2	1	31.20	3.58	37	6
22	Nagthana	Yes	3	1	257	492	733	438.00	59.75	3	1	41.00	8.33	52	20
23	Harani	Yes	12	7	660	1836.59	1915	3530.00	184.33	3	2	243.20	13.24	231	35
24	Yamai	Yes	2	2	147	492.44	331	748.00	225.98	2	2	55.70	11.31	48	33
25	Mohri	Yes	1	1	920	357	310	282.00	90.85	3	3	30.00	8.40	85	9
26	Galan	Yes	1	1	320	340	645	537.50	83.33	5	5	44.00	12.94	30	9
27	Anji Bhorkhed	Yes	1	1	284	595.77	430	192.32	44.73	5	5	13.80	2.32	18	6
	2009-10														
	Minor														
28	Pilanwadi	Yes	1	1	514	419.00	317	220.20	69.46	3	2	130.70	31.19	340	66
29	Shendhri	Yes	1	1	1461	314	905	243.24	26.88	4	4	53.00	16.88	134	9
30	Dighanchi	Yes	1	1	722	742	13393	940.00	7.02	2	2	52.00	7.01	105	15
31	Kuchi	Yes	1	1	650	392	2219	56.62	2.55	1.00	1.00	10.00	2.55	14.00	2
32	Lingnur	Yes	1	1	680	307.6	1995	486.00	24.36	2.00	1.00	75.00	24.38	60.00	9
33	Pathari	Yes	2	2	772	1114.42	2569	154.62	6.02	2	1	20.00	1.79	46	6
34	Padvalkarwadi	Yes	2	2	597	475	370	97.60	26.41	2	1	78.80	16.59	76	13
35	Hotagi	Yes	2	2	792	1199	1794	1296.00	72.26	2	2	104.20	8.69	68	9
36	Mozari	Yes	1	1	297	583.00	933	719.00	77.03	6	2	31.85	5.46	15	5

Sr. No	Name of Project	Whether included in MWSIP	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement for the HW season 2011 (Thousand Cum)	Water Delivered in Hot Weather (Thousand Cum)	% of water delivered in HW to Applicable Entitlement	No of rotations in the HW season 2011	No of visit by regulator in the HW season 2011	Actual area irrigated in the HW season 2011 (ha)	% of Irrigated area to WUA area	No. of farmers taken up Irrigation in the HW season 2011	% of farmers taken up Irrigation to total farmers under WUA
37	Pimpalgaon Hande	Yes	1	1	122	239.25	0.52	0.20	38.00	6	1	5.28	2.21	5	4
38	Motsawanga	Yes	1	1	509	864	190	185.00	97.37	6	5	46.00	5.32	52	10
39	Kasarbalkunda	Yes	2	1	562	834	1224	20.04	1.64	2	1	9.40	1.13	18	3
40	Bhalwani	Yes	1	1	932	650	364	530.00	145.60	3	3	100.00	15.38	90	10
41	Tikhol	Yes	1	1	860	340	408	530.00	129.90	3	3	105.00	30.88	120	14
42	Ekalhare	Yes	1	1	133	351	1770	291.66	16.48	2	1	75.00	21.37	40	30
43	Chougaon	Yes	1	1	790	490	1180	86.07	7.29	2	0	105.00	21.43	10	1
44	Kothare	Yes	1	1	784	737	240	239.62	99.84	1	0	152.00	20.62	151	19
	2010-11														
	Major														
45	Upper Pus	Yes	30	30	6605	11814.00	25176.00	20447.00	81.22	7	7	683.95	5.79	805	12
	Medium														
46	Krishna Canal	Yes	25	5	3502	1038.98	3349	987.00	29.47	7	7	118.00	11.36	1312	37
	Minor														
47	Shirsuphal	Yes	1	1	1155	661	2885	526.00	18.23	2	4	105.80	16.01	257	22
48	Shegaon	Yes	1	1	2013	843	1915	1818.00	94.93	6.00	2.00	95.00	11.27	216.00	11
49	Kandalgaon	Yes	1	1	1131	448.00	530	430.00	81.13	3	9	12.21	2.73	74	7
50	Karanjivane	Yes	1	1	314	269	661	315.63	47.75	3	6	45.00	16.73	165	53

Sr. No.	Name of Project	Whether included in MWSIP	No of WUAs in the Project	WUAs under Entitlement.	No. of farmers under WUA	Area Under WUA in ha.	Applicable Entitlement for the HW season 2011 (Thousand Cum)	Water Delivered in Hot Weather (Thousand Cum)	% of water delivered in HW to Applicable Entitlement	No of rotations in the HW season 2011	No of visit by regulator in the HW season 2011	Actual area irrigated in the HW season 2011 (ha)	% of Irrigated area to WUA area	No. of farmers taken up Irrigation in the HW season 2011	% of farmers taken up Irrigation to total farmers under WUA
51	Rampur	Yes	1	1	365	486.4	204	334.00	163.73	2	2	75.90	15.60	96	26
52	Ghoddhari	Yes	1	1	405	498	965	919.00	95.23	8	1	136.00	27.31	90	22
53	Amboli	Yes	1	1	2129	607	1260	86.00	6.83	2	1	13.00	2.14	30	1
54	Legam	Yes	1	1	672	383.51	544	544.00	100.00	9	8	19.68	5.13	20	3
	Grand Total		708	268	125817	115306.8	201563.203	126087.17				17470.32		14791	